Exova Warringtonfire Holmesfield Road Warrington WA1 2DS United Kingdom T:+44 (0) 1925 655 116 F:+44 (0) 1925 655 419 E:warrington@exova.com W:www.exova.com



Title:

Indicative Fire Test

WF Report No:

334623/B



Prepared for:

Intumescent Systems Ltd

Envirograf House Barfrestone Dover Kent CT15 7JG

Date: 19th December 2013

Indicative Fire Test

We have pleasure in enclosing the information obtained from the indicative fire test conducted, on your behalf, on the 1st November 2013.

The test results relate to an investigation, which utilised the heating and pressure conditions specified in BS EN 1363-1: 2012. The information is provided for the test sponsor's information only and should not be used to demonstrate performance against any published fire test standard, nor compliance with a regulatory requirement.

The test was not conducted under the requirement of UKAS accreditation.

The purpose of the investigation was to provide an indication of the ability of a penetration sealing system to maintain the fire resistance of a plasterboard partition where it has been penetrated by PVC air conditioning trunking, when subjected to the heating and pressure conditions specified by BS EN 1363-1: 2012.

The test assembly consisted of a plasterboard partition of overall nominal dimensions of 1500 mm high by 1500 mm wide by 100mm thick penetrated by two sections of galvanised steel trunking. The partition comprised a galvanised mild steel framework lined on each face by 2 layers of 12.5 mm thick 'Type F' gypsum board. Three PVC air conditioning trunkings where tested two at 204mm by 60mm cross-sectional area and the other at 220mm by 90mm cross-sectional area. The smaller of the two sizes was tested in a vertical and horizontal orientation. For the purpose of the test the specimen PVC air conditioning trunkings were referenced A, D and E. Other test specimens where incorporated in the test and these are reported separately.

Specimen A consisted of a PVC air conditioning trunking 204mm wide by 60mm high. The trunking was provided with consisted of two layers of 3mm thick Envirograf Multigraf intumescent sheet; one layer of No.3 grade and one layer No.2 grade wrapped in aluminium foil with an outer layer of Envirograf foiled FB70 cloth.

Specimen E consisted of a PVC air conditioning trunking 204mm high by 60mm wide. The trunking was provided with consisted of two layers of 3mm thick Envirograf Multigraf intumescent sheet; one layer of No.3 grade and one layer No.2 grade wrapped in aluminium foil with an outer layer of Envirograf foiled FB70 cloth.

Specimen D consisted of a PVC air conditioning trunking 220mm high by 90mm wide. The trunking was provided with an 'Envirograf Firoblok Ref:110V29'. The Firoblok consisted of 3 layers of 3mm thick Envirograf Multigraf No. 3 intumescent sheet material wrapped in aluminium foil with an outer layer of Envirograf foiled FB70 cloth.

The test construction was mounted such that it formed the front vertical face of a 1.5 m by 2.0 m gas fired furnace chamber, the temperature rise of which was controlled to conform with the heating and pressure conditions specified in BS EN 1363-1: 2012.

The following information relating to the test is enclosed:

- ◆ Table 1 Specified and actual furnace temperatures and percentage tolerances
- ♦ Table 2 Individual and mean temperatures recorded on the unexposed surface of Specimen A. (Thermocouples 20 and 21)
- ♦ Table 3 Individual temperatures recorded on the unexposed surface of Specimen D. (Thermocouples 26 and 27)
- ♦ Table 4 Individual temperatures recorded on the unexposed surface of Specimen E. (Thermocouples 28 and 29)
- ♦ Graph 1 Graph showing the specified and actual furnace temperatures

- Observations on the general behaviour of the specimens during the test.
- ♦ Photographs taken before, during and after the test.

The test was discontinued after a period of 130 minutes.

We trust that the information obtained from the test will be useful to you.

Responsible Officer

G. Edmonds

Senior Testing and Auditing Officer

Fire Resistance Department

G.A. Eang

Exova Warringtonfire

This copy has been produced from a .pdf format electronic file that has been provided by Exova Warringtonfire to the sponsor of the report and must only be reproduced in full. Extracts or abridgements of reports must not be published without permission of **Exova Warringtonfire**. The pdf copy supplied is the sole authentic version of this document. All pdf versions of this report bear authentic signatures of the responsible **Exova Warringtonfire** staff.

Table 1

Time	Specified	Actual	
I IIIIe	Furnace	Furnace	
Minutes			
Minutes	Temperature	Temperature	
	Deg. C	Deg. C	
0 5	20	15	
5	576	595	
10	678	667	
15	739	737	
20	781	782	
25	815	818	
30	842	840	
35	865	864	
40	885	887	
45	902	910	
50	918	925	
55	932	931	
60	945	945	
65	957	958	
70	968	969	
75	979	979	
80	988	989	
85	997	999	
90	1006	1007	
95	1014	1011	
100	1022	1022	
105	1029	1030	
110	1036	1036	
115	1043	1044	
120	1049	1049	
125	1055	1053	
130	1061	1080	

Table 2

Time	T/C	T/C
	Number	Number
Minutes	20	21
	Deg. C	Deg. C
0	15	15
5	16	63
10	27	61
15	43	45
20	53	36
25	57	33
30	60	32
35	63	32
40	64	32
45	65	33
50	64	34
55	63	34
60	61	35
65	60	35
70	59	34
75	61	33
80	62	33
85	65	33
90	66	33
95	67	34
100	69	34
105	70	35
110	71	36
115	72	36
120	73	37
125	73	37
130	73	38


Table 3

Time	T/C	T/C	
	Number		
Minutes	26	Number 27	
	Deg. C	Deg. C	
0	13	13	
5	15	44	
10	16	54	
15	24	46	
20	36	44	
25	44	43	
30	55	43	
35	57	43	
40	63	44	
45	62	45	
50	58	45	
55	58	45	
60	60	46	
65	62	47	
70	65	48	
75	69	49	
80	74	50	
85	76	51	
90	76	51	
95	76	53	
100	78	54	
105	79 55		
110	80	58	
115			
120			
125	86	67	
130	86	70	

Table 4

Time	T/C	T/C	
	Number	Number	
Minutes	28	29	
	Deg. C	Deg. C	
0	14	14	
5	16	71	
10	23	67	
15	31	49	
20	45	43	
25	53	41	
30	58	40	
35	63	41	
40	63	42	
45	65	43	
50	67	44	
55	67	46	
60	69	49	
65	71	52	
70	73	55	
75	74	59	
80	75	60	
85	77	63	
90	77	62	
95	78	63	
100	79	64	
105	80	67	
110	80	68	
115	80	69	
120	82	70	
125	84	71	
130	86	72	

Graph 1




Test Observations

Time		
mins	secs	
00	00	The test commences.
03	00	Copious amounts of smoke are being released form Specimen Duct E.
04	00	Smoke release from Specimen duct E decreases.
06	00	Fair amount of smoke release from Specimen duct A.
10	00	All of the plastic ducts have burnt away on the exposed face.
15	00	There are no visible significant changes to the test specimens on the unexposed face.
40	00	There are no visible significant changes to the unexposed face of the specimen.
50	00	The partition and steel trunking are radiating on the exposed face.
60	00	The partition, where it has been penetrated by the steel trunking, is satisfying the specified performance criteria with regards to through gaps, sustained flaming and cotton pad ignition on the unexposed face.
76	00	A small section of the intumescent material is being forced out from the underside of Specimen D.
90	00	The partition, where it has been penetrated by the steel trunking, is satisfying the specified performance criteria with regards to through gaps, sustained flaming and cotton pad ignition on the unexposed face.
110	00	Therefore no visible significant changes to the unexposed and exposed faces of the test construction.
120	00	The partition, where it has been penetrated by the steel trunking, is satisfying the specified performance criteria with regards to through gaps, sustained flaming and cotton pad ignition on the unexposed face.
128	00	Some small sections of intumescent material are falling away from Specimens D and E.
130	00	The partition, where it has been penetrated by the steel trunking, is satisfying the specified performance criteria with regards to through gaps, sustained flaming and cotton pad ignition on the unexposed face.

Test Photographs


The exposed face of the test construction prior to the test.




The unexposed face of the test construction after 20 minutes of testing.




The unexposed face of the test construction after 30 minutes of testing



The unexposed face of the test construction after 71 minutes of testing




The unexposed face of the test construction after 76 minutes of testing



The unexposed face of the test construction after 80 minutes of testing



The unexposed face of the test construction after 95 minutes of testing




The unexposed face of the test construction after 103 minutes of testing



The unexposed face of the test construction after 120 minutes of testing



The unexposed face of the test construction after 130 minutes of testing



The exposed face of the test construction shortly after the test

